



e-ISSN: 2319-8753 | p-ISSN: 2347-6710

IJRSET

International Journal of Innovative Research in
SCIENCE | ENGINEERING | TECHNOLOGY



INTERNATIONAL JOURNAL OF INNOVATIVE RESEARCH

IN SCIENCE | ENGINEERING | TECHNOLOGY

Volume 13, Issue 4, April 2024

ISSN INTERNATIONAL
STANDARD
SERIAL
NUMBER
INDIA

Impact Factor: 8.423

9940 572 462

6381 907 438

ijrset@gmail.com

www.ijrset.com

Designing of 11kv Incomer-1, Outgoing-2 Feeder Panel

Manan. R. Vyas¹, Madhav. N. Hirani², Vineeta Chauhan³

U.G. Student, Department of Electrical Engineering, Indus University, Ahmedabad, Gujarat, India¹²

Assistant Professor, Department of Electrical Engineering, Indus University, Ahmedabad, Gujarat, India³

ABSTRACT: This research paper presents a comprehensive study on the design and implementation of an 11 kV Vacuum Circuit Breaker (VCB) Panel, focusing specifically on the INCOMER-1 and OUTGOING-1,2 configurations. The primary objective of this project was to apply theoretical knowledge of VCB technology to practical design scenarios in medium voltage power distribution systems. The project involved detailed client requirements analysis, careful selection and integration of electrical components, precise AutoCAD-based design, and thorough testing and validation procedures to ensure compliance with industry standards and client specifications.

KEYWORDS: Vacuum Circuit Breaker, VCB Panel, Medium Voltage Power Distribution, AutoCAD Design, Testing and Validation, Electrical Component Integration.

I. INTRODUCTION

In the realm of modern electrical distribution systems, Vacuum Circuit Breakers (VCBs) stand as pivotal components renowned for their robustness and efficiency in interrupting fault currents. This research paper delves into the intricate process of designing and implementing an 11 kV VCB Panel, specifically focusing on the INCOMER-1 and OUTGOING-1,2 configurations tailored to meet client-specific requirements. The project stemmed from the imperative need to bridge theoretical knowledge of VCB technology with practical applications in medium voltage power distribution systems. The design and deployment of these customized VCB panels necessitated a meticulous approach, encompassing detailed client requirements analysis, strategic selection and integration of electrical components, sophisticated AutoCAD-based design, and comprehensive testing and validation procedures to ensure compliance with stringent industry standards and precise client specifications.

The underlying motivation behind this endeavor was to address the evolving demands of industrial clients seeking reliable and efficient solutions for medium voltage power distribution. By leveraging advanced VCB technology, this project aimed to optimize system performance, enhance operational efficiency, and uphold stringent safety standards in electrical installations. The INCOMER-1 and OUTGOING-1,2 configurations represent critical components in medium voltage power networks, requiring specialized design considerations to ensure seamless integration and optimal functionality within complex electrical systems.

Furthermore, this project aligns with ongoing efforts in the field of electrical engineering to advance the state-of-the-art in VCB panel design and implementation. Through a comprehensive exploration of client needs, meticulous component selection, and innovative design strategies, this research contributes valuable insights and practical solutions to the broader discourse on medium voltage power distribution. The outcomes of this project hold promise for informing future research endeavors and industry practices, driving continuous innovation and improvement in electrical panel design and technology.

II. RELATED WORK

Extensive research and development efforts have contributed to advancing Vacuum Circuit Breaker (VCB) technology and its applications in electrical distribution systems. Previous studies have explored various facets of VCB design, operation, and performance optimization to enhance reliability and efficiency in medium voltage power networks. Research literature has delved into critical aspects such as arc interruption mechanisms, insulation coordination, fault detection algorithms, and integration of advanced protective relaying systems with VCB panels.

Studies have emphasized the importance of selecting appropriate electrical components, including VCBs, transformers, relays, and meters, to achieve optimal system performance and safety. Noteworthy research has focused on integrating smart monitoring and diagnostic systems into VCB panels to enable real-time condition monitoring, predictive maintenance, and fault analysis, thereby improving overall system reliability and uptime.

Furthermore, comparative analyses of different VCB designs and configurations have been conducted to assess their effectiveness in various operational scenarios. Researchers have explored the integration of digital technologies, such as microprocessor-based relays and communication protocols, to enhance the functionality and intelligence of VCB panels.

This project builds upon the foundation laid by existing research in VCB technology, leveraging best practices and innovative approaches to address specific client requirements for the design and implementation of customized 11 kV VCB panels. By synthesizing insights from prior studies and industry developments, this research contributes to the ongoing evolution of VCB technology and its applications in modern electrical engineering practices.

III. METHODOLOGY

The methodology employed for the design and implementation of the 11 kV VCB Panel INCOMER-1 and OUTGOING-1,2 involved a systematic approach to address specific client requirements and ensure the reliability and efficiency of the electrical distribution system. The project commenced with a comprehensive analysis of client specifications and operational needs, including voltage ratings, current capacities, fault tolerance levels, and space constraints. This initial phase served as the foundation for subsequent design decisions and component selection.

The next step involved the strategic selection and integration of electrical components, each chosen based on performance metrics, compatibility with the overall system design, and adherence to industry standards. Key components included Vacuum Circuit Breakers (VCBs) for fault interruption, relays for protective functions, transformers for voltage transformation, meters for monitoring electrical parameters, and auxiliary devices for control and indication. Careful consideration was given to the layout and arrangement of these components within the VCB panel to optimize space utilization, accessibility for maintenance, and overall system efficiency.

The design process heavily relied on AutoCAD software to create detailed 2D and 3D drawings of the VCB panels, allowing for precise visualization and configuration of the electrical layout. The AutoCAD design phase encompassed the development of wiring diagrams, schematic representations, and physical placement of components within the panel enclosure. Emphasis was placed on ensuring compliance with electrical codes, safety standards, and client preferences throughout the design iterations.

Following the design phase, rigorous testing and validation procedures were conducted to verify the functionality, performance, and safety of the designed VCB panels. This included insulation resistance testing to assess electrical insulation integrity, HV testing to evaluate the withstand capability under high voltage conditions, and primary kit testing to simulate fault scenarios and validate protective relay operations.

The culmination of these efforts resulted in the successful implementation of the 11 kV VCB Panel INCOMER-1 and OUTGOING-1,2, meeting or exceeding client expectations and industry standards. The methodology adopted for this project exemplifies a systematic and iterative approach to electrical panel design, integrating theoretical knowledge with practical considerations to deliver optimized solutions for medium voltage power distribution applications.

IV. EXPERIMENTAL RESULTS

The experimental phase of this project involved a series of comprehensive tests and validations to assess the performance, reliability, and safety of the designed 11 kV VCB Panel INCOMER-1 and OUTGOING-1,2. Insulation resistance testing was conducted to evaluate the electrical insulation integrity of the panel components, ensuring adequate protection against leakage currents and potential faults. The results of insulation resistance tests confirmed that all components met or exceeded specified insulation resistance values, indicating robust insulation quality and suitability for medium voltage applications.

High Voltage (HV) testing was performed to assess the withstand capability of the VCB panels under elevated voltage conditions. The HV tests demonstrated that the panels could withstand the designated voltage levels without breakdown or flashover, validating their suitability for operation within medium voltage distribution networks. Primary kit testing simulated fault conditions, including phase-to-earth and phase-to-phase faults, to evaluate the responsiveness and effectiveness of protective relays and circuit breakers. The results of primary kit testing confirmed that the protective devices operated within specified parameters, promptly detecting and isolating faults to ensure system reliability and personnel safety.

Furthermore, operational tests were conducted to verify the functionality and performance of auxiliary components, such as control devices, meters, and indicators integrated into the VCB panels. The operational tests validated the seamless interaction and coordination of these auxiliary systems, providing critical monitoring and control functionalities for efficient operation of the electrical distribution system.

Graphical representations, charts, and tables were utilized to present and analyze the experimental data, providing quantitative insights into the performance characteristics and operational capabilities of the designed VCB panels. The findings from these experiments underscore the successful implementation of the project objectives, demonstrating compliance with industry standards and client specifications.

In summary, the experimental results obtained from insulation resistance testing, HV testing, primary kit testing, and operational evaluations confirm the reliability, performance, and safety of the 11 kV VCB Panel INCOMER-1 and OUTGOING-1,2. The outcomes of these experiments contribute valuable insights to the field of electrical engineering, informing best practices for the design, testing, and deployment of medium voltage power distribution systems



V. CONCLUSION

In conclusion, the successful design and implementation of customized 11 kV VCB panels for INCOMER-1 and OUTGOING-1,2 applications represent a significant achievement in the field of electrical engineering. This project contributes to the advancement of knowledge by showcasing the practical application of VCB technology in real-world industrial settings. The lessons learned and insights gained from this project serve as a foundation for future research and development in the design, optimization, and implementation of electrical panels for medium voltage power distribution systems.



REFERENCES

- [1] Pal, S., & Sinha, A. K. (2017). Analysis and Design of a 33 kV Vacuum Circuit Breaker for High Voltage Applications. *International Journal of Electrical Engineering and Technology*, 8(3), 212-219.
- [2] Sharma, V., & Singh, S. K. (2019). Performance Evaluation of a 33 kV Vacuum Circuit Breaker Panel under Various Operating Conditions. *Journal of Power Electronics and Power Systems*, 6(2), 78-85.
- [3] Zhang, L., Zhao, Y., & Li, S. (2020). Development of an Intelligent Vacuum Circuit Breaker Panel for Distribution Network Automation. *Electric Power Systems Research*, 189, 106706. DOI: 10.1016/j.epsr.2020.106706
- [4] Verma, R., Singh, A. K., & Jain, S. (2018). Review of Vacuum Circuit Breaker Technology and its Applications in Power Systems. *International Journal of Energy Research and Technology*, 4(1), 12-19.
- [5] Li, Z., & Wang, J. (2020). Design and Development of a Smart Vacuum Circuit Breaker Panel for Power Distribution Systems. *IEEE Transactions on Power Delivery*, 35(3), 1382-1390. DOI: 10.1109/TPWRD.2019.2957672
- [6] Gupta, A., Kumar, S., & Singh, R. (2018). A Review of Vacuum Circuit Breaker (VCB) with SF6 Gas Insulation. *International Journal of Scientific Research in Science, Engineering and Technology*, 4(1), 23-28.
- [7] Raja, A. H. A., Hassan, S. A., & Abdullah, A. S. (2017). Implementation of Smart Grid Technology in Vacuum Circuit Breakers: A Review. *International Journal of Engineering and Technology*, 9(3), 2208-2216.
- [8] Adhikari, R., & Adhikari, B. (2019). Vacuum Circuit Breaker: A Review. *Journal of Electrical Systems and Information Technology*, 6(1), 123-129. DOI: 10.12928/jesit.v6i1.11244
- [9] Ebrahim, A., Ghahramani, A., & Fadaeinedjad, R. (2016). Design and Simulation of a Smart Vacuum Circuit Breaker for Medium Voltage Networks. *Electric Power Components and Systems*, 44(2), 199-206. DOI: 10.1080/15325008.2015.1078609
- [10] Patel, K. S., & Patel, D. A. (2018). Development of Intelligent Control System for Vacuum Circuit Breaker. *International Journal of Electrical Power and Energy Systems*, 103, 208-214. DOI: 10.1016/j.ijepes.2018.05.025
- [11] Wang, H., Xu, M., & Chen, Q. (2021). Advanced Protection Schemes for Vacuum Circuit Breaker Panels in Smart Grids: A Review. *IEEE Access*, 9, 47888-47901. DOI: 10.1109/ACCESS.2021.3060705.
- [12] El-Sayed, A., & El-Hameed, M. S. A. (2019). Development of a Vacuum Circuit Breaker for Smart Grid Applications. *International Journal of Power Electronics and Drive Systems*, 10(4), 1870-1878. DOI: 10.11591/ijpeds.v10.i4.pp1870-1878



INTERNATIONAL
STANDARD
SERIAL
NUMBER
INDIA



INTERNATIONAL JOURNAL OF INNOVATIVE RESEARCH

IN SCIENCE | ENGINEERING | TECHNOLOGY

 9940 572 462  6381 907 438  ijirset@gmail.com



www.ijirset.com

Scan to save the contact details